



## FINAL APPROVAL FOR STORMWATER AND SEDIMENT CONTROL


PRD No: 18-PR-0048  
Description: Towson Roundabout to Newell Avenue 16"  
Water Transmission Main and Resurfacing  
Design Firm: McCormick Taylor, RJM Engineering

Contract No: BA9825377  
Road: MD 45  
Date Submitted: 04/07/2025

Final Approval for stormwater management and sediment control is hereby granted to the Maryland Department of Transportation State Highway Administration (MDOT SHA) in compliance with Environment Article, Section 4-106 and 4-205 Annotated Code of Maryland. Final Approval is based on the Project Data Summary and is subject to the following conditions:

1. This approval shall become null and void if the construction authorized herein has not been completed within three years from the granting of this approval unless an extension has been requested, and is granted, by the MDOT SHA Plan Review Division (PRD).
2. This approval is subject to all laws and regulations now in effect and may be revoked if it is subsequently determined that this authorization violates other laws of the State.
3. The location and dimensions of all sediment control structures, stormwater management facilities, grading, excavation, and fill shall be in accordance with the latest approved plans. Changes to the approved plans requires written approval from PRD. The field office shall have a copy of this approval, the associated plans, and copies of any approved modifications available at the construction site for reference during the construction period. Contractor requests for minor field changes to erosion and sediment control should be submitted online through the MDOT SHA Quality Assurance Toolkit.
4. Off-site borrow or waste sites located on private property require Soil Conservation District approval and may require local and county approvals. Sites located on State property require PRD approval. Maryland Department of the Environment (MDE) approval is required for sites located on federal property. Local approval numbers for off-site borrow or waste sites shall be furnished to the MDOT SHA Quality Assurance Division (QAD) Representative.
5. The authorized MDOT SHA agent shall notify the MDOT SHA QAD at (410) 365-0164, at least seven days prior to initiation of the project, and within five days after the construction activities end.
6. Projects with a Limit of Disturbance (LOD) of 1.0 acres or greater require an approved Notice of Intent (NOI) from MDE prior to the start of construction.
7. For projects that include the construction of new stormwater management facilities, as-builts must be completed and approved prior to the project closeout.

Approved By: \_\_\_\_\_

  
Jeffrey Knaub, P.E., Chief  
Plan Review Division

Date: 4/7/25

**Project Data Summary**

Points of Investigation (POI/LOI)	1 (Project Site)
IART/IAT	0.00/0.00 Acres
Limit of Disturbance (LOD)	1.18 Acres
Water Quality (WQv)	A 3.3.A waiver has been requested and is approved based on the proposed improvements being considered maintenance work for the ADA sidewalk and drainage repairs and replacements. The quantity of proposed pavement is considered de minimis and there are no changes to the site hydrology as a result of these improvements.
Patapsco River Area (02-13-09)	0.00 Acre Credit
Channel Protection Volume (Cpv)	Not Required
Water Quantity Control (Qp/Qf)	Not Required
Pond Code 378 / Dam Safety	Not Applicable